

**ADDENDUM NO. 2**

**To the Plans, Specifications, Proposal and Contract**

**FOR THE**

**CITY OF BOTHELL**

**North Creek Trail Section 4 Phase 2 and Phase 3**

ISSUED THIS DATE: 12/15/2022

BID OPENING: 2:30 PM on December 20, 2022

Public Works Department  
18415 101<sup>st</sup> Ave NE  
Bothell, WA 98011

**TO PROSPECTIVE BIDDERS:**

The attention of all bidders is directed to the additions and modifications described in this Addendum which shall be considered as part of the Contract Documents for the North Creek Trail Section 4 Phase 2 and Phase 3 project. **All bidders must acknowledge receipt of this Addendum to the Contract Documents on Page 2-1 of the Bid Proposal.**

**I. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE CONTRACT PROVISIONS**

**ITEM NO. 1 – SECTION 8-20, SPECIAL PROVISIONS, DIVISION 8, MISCELLANEOUS CONSTRUCTION, SECTION 8-20.3(5) CONDUIT**

SUPPLEMENT

Section 8-20.3(5) of the Special Provisions

WITH

“Lowering Conduits to Accommodate Moment Slab

There are two 2" PVC conduits that need to be lowered per Construction Note 12 on sheet IL1 of the Plans.

The copper interconnect cable in one of the conduits shall be disconnected at the existing splice in the existing junction box at approx. Station 10+00 and pulled out from the existing junction box at approximate Station 15+00 prior to conduit modifications. Contractor shall reinstall the copper interconnect after conduit modifications and restore splices at the existing box at approx. Station 10+00. Contractor shall provide 2 weeks' notice to the Engineer prior to interconnect outage to coordinate with Snohomish County Signals staff.

The existing illumination wires in the other conduit shall be removed and replaced between the existing junction boxes at approx. Stations 13+25 and 16+25 to allow the conduit modifications per

Construction Note 12 on sheet IL1 and spliced back to existing conductors in said junction boxes. Existing illumination system shall be maintained operational during all hours of darkness.”

ITEM NO. 2 – SECTION 8-20, SPECIAL PROVISIONS, DIVISION 8, MISCELLANEOUS CONSTRUCTION, SECTION 8-20.4 MEASUREMENT

SUPPLEMENT

Section 8-20.4 of the Special Provisions

WITH

“Lowering of conduits to accommodate the moment slab, and associated illumination and interconnect wiring removal and restoration will not be specifically measured, but shall be included in the “Illumination System Modification, Complete” lump sum bid item.”

ITEM NO. 3 – SECTION 6-13, SPECIAL PROVISIONS, DIVISION 6, STRUCTURES, SECTION 6-13.2 MATERIALS

REPLACE

“MSE wall block units shall have a minimum 28-day compressive strength of 2,200 psi. The maximum absorption of 10 pcf and adequate freeze-thaw protection (absorption by weight = 6%) shall, in general, satisfy the listed ASTM standards (C140 and C1262).”

WITH

“MSE wall block units shall be cast with Class 4000 psi concrete, conforming to the air content requirements of Section 6-02.3(2)A. Blocks will be accepted based on visual inspection, and conformance to Section 6-02.3(9) and the specified concrete strength and air content requirements.”

Attachments:  
None